

ZILHA PARISHAD BULDANA

WORKS DIVISION BULDANA

PANCHAYAT SAMITI BULDANA

ESTIMATE

- Name of Work -

**CONSTRUCTION OF OOTA INFRONT OF DR. BABASAHEB
AMBEDKAR STATUE PREMISES AT VILLAGE SAKHALI KHURD
TQ.+DIST BULDANA**

ESTIMATE COST IN Rs.

200000.00

FUND HEAD :- प्रधानमंत्री आदर्श ग्राम योजना

ESTIMATE

Division :- Z.P. Works Buldana S.No. 90 / SUE/W.D.Z.P. Sub-Div. Buldana
Sanctioned Estimate No. :- Technically Sanctioned for Rs. 200000/-
(In word Rs. Two lacs only)
Fund Head :-
Minor Head :-
Major Head :- प्रधानमंत्री आदर्श ग्राम योजना
Service Head :-
Departmental Head :-

Sub-Divisional Officer
W.D.Z.P. Sub-Division
Buldana

Estimate framed in the office of The Executive Engineer Zilla Parishad Works Division Buldana and the propable expenses that will be incurred in

Name Of Work :- CONSTRUCTION OF OOTA INFRONT OF DR. BABASAHEB AMBEDKAR STATUE PREMISES AT VILLAGE SAKHALI KHURD TQ.+DIST BULDANA

Rs. 200000

Administratively Approved Under

Technically Sanctioned under
No and dated.....

Estimate prepared by :- Shri. M.R.Zine Sect. Engineer P.S. Buldana
Estimate Checked by :- Shri.
Call of Authority :-

GENERAL DESCRIPTION

(Attached Seperately)

Sect. Engineer

Block Development Officer
Panchayat Samiti Buldana

293

Name Of Work :- CONSTRUCTION OF OOTA INFRONT OF DR.
BABASAHEB AMBEDKAR STATUE PREMISES AT
VILLAGE SAKHALI KHURD TQ.+DIST BULDANA

RECAPITULATION SHEET

Name of work		Total Estimate Cost Rs.	
1	CIVIL COST OF WORK As Per Abstract -B	Rs.	162193
2	Add 18% GST On Cost Of Work	Rs.	29195
3	Add For Royalty Charges & Material Testing Charges (Abstract-C)	Rs.	7044
4	Add For 0.50% Labour Insurance	Rs	811
5	Add for SQM Charges	Rs	500
6	Add For Contengencis	Rs	257
TOTAL		Rs.	200000
GRAND TOTAL (SAY)		Rs.	200000

Sect. Engineer

**CONSTRUCTION OF OOTA INFRONT OF DR. BABASAHEB AMBEDKAR STATUE
PREMISES AT VILLAGE SAKHALI KHURD TQ.+DIST BULDANA**

ABSTRACT SHEET (B)

Item No.	Particulars	Quantity	Unit	Rate	Amount
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means SSR Item No.- 21.02	7.88	Cum	207.00	1631.00
2	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete. SSR Item No.- 21.38	3.76	Cum	1704.00	6407.00
3	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) SSR Item No.- 24.01	3.08	Cum	6611.25	20363.00
4	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite/quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction and roughening the surface if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) SSR Item No.- 25.50	1.48	Cum	13037.15	19295.00
5	Providing fly ash brick masonry with conventional / I.S. type fly ash bricks in C.M. 1:6 in foundation and plinth including bailing out water manually striking joints, racking out joints watering and scaffolding etc. complete. SSR Item No.- 27.12	2.46	Cum	7598.60	18693.00
6	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete. SSR Item No.- 21.37	16.28	Cum	851.00	13854.00
7	Providing and laying Cast in situ/Ready Mix cement concrete M-15 of trap/ granite/quartzite/gneiss metal for coping to plinth or parapet, moulded or chamfered as per drawing or as directed including steel centering, plywood/ steel formwork SSR Item No.- 24.16	0.49	Cum	7255.90	3555.00

**CONSTRUCTION OF OOTA INFRONT OF DR. BABASAHEB AMBEDKAR STATUE
PREMISES AT VILLAGE SAKHALI KHURD TQ.+DIST BULDANA**

ABSTRACT SHEET (B)

Item No.	Particulars	Quantity	Unit	Rate	Amount
8	Providing and fixing in position TMT · FE · 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, SSR Item No.- 26.33	0.22	MT	89948.45	19789.00
9	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at SSR Item No.- 32.11	10.04	Sqm	675.95	6778.00
10	Providing and applying two coats of water proof cement paint of approved manufacture and of approved colour to old plastered SSR Item No.- 35.14	20.09	Sqm	78.00	1567.00

Total Rs 162193.00

Sectional Engineer

NAME OF WORK

**CONSTRUCTION OF OOTA INFRONT OF DR. BABASAHEB
AMBEDKAR STATUE PREMISES AT VILLAGE SAKHALI KHURD
TQ.+DIST BULDANA**

ABSTRACT SHEET {C}

Sr.No	Item Of Work	Qty.	Unit	Rate	Amount (Rs.)
1	2	3	4	5	6
1	Total Royalty Charges For Sand With 2% Surcharge & 10% Distt. Mineral Foundation Cess	4.60	Cum	237.37 ✓	1091
2	Total Royalty Charges For other Minerals With 2% Surcharge	20.041	Cum	216.18 ✓	4333
3	Testing Charges for Sand	1	No	895.00 ✓	895
4	Testing Charges for Concrete M20	1	No	725.00	725
	Total Cost Of Royalty & Testing Charges				7044 ✓

Sect. Engineer

NAME OF
WORK

CONSTRUCTION OF OOTA INFRONT OF DR. BABASAHEB AMBEDKAR STATUE
PREMISES AT VILLAGE SAKHALI KHURD TQ.+DIST BULDANA

MEASUREMENTS

Item	Item Of Work.	No	Length	Width	Depth	Quantity	Unit
1	2	3	4	5	6	7	8

- 1 Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means

SSR Item No.- 21.02

OOTA

Beam	2	4.50	0.30	0.15	0.41		
	2	6.20	0.30	0.15	0.56		
Column Pit	4	1.20	1.20	1.20	6.91		
						7.88	Cum

- 2 Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.

SSR Item No.- 21.38

OOTA

Plinth	1	6.20	4.04	0.15	3.76		
						3.76	Cum

- 3 Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)

SSR Item No.- 24.01

OOTA

Pcc	1	6.20	4.04	0.10	2.50		
Column Pit	4	1.20	1.20	0.10	0.58		
						3.08	Cum

- 4 Providing and laying in situ /Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including bailing out water, Steel centering formwork, laying/pumping cover blocks, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)

SSR Item No.- 25.11

OOTA

Column C	0.23X0.30	4	0.90	0.90	0.30	0.97	
						0.97	Cum

- 5 Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. columns as per detailed designs and drawing or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete.(Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)

SSR Item No.- 25.31

Column	Upto	C	0.23X0.30	4	0.23	0.30	0.80	0.22		
	GL									
Column	Upto	C	0.23X0.23	4	0.23	0.23	0.90	0.19		
	Oota									
	Level									
									0.41	Cum

Item No.	Item Of Work.	No	Length	Width	Depth	Quantity	Unit
1	2	3	4	5	6	7	8

- 4 Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite/quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction and roughening the surface if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel) with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)

SSR Item No.: 25.50

Ground Beam	GB1 · 0.23X0.30	2	4.50	0.23	0.30	0.62	
	GB2 · 0.23X0.30	2	6.20	0.23	0.30	0.86	
						1.48	Cum

- 5 Providing fly ash brick masonry with conventional / I.S. type fly ash bricks in C.M. 1:6 in foundation and plinth including bailing out water manually striking joints, racking out joints watering and scaffolding etc. complete.

SSR Item No.: 27.12

OTA	Walls	2	6.20	0.23	0.50	1.43	
		2	4.50	0.23	0.50	1.04	
						2.46	Cum

- 6 Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete.

SSR Item No.: 21.37

OTA	Plinth Filling	1	6.20	4.04	0.65	16.28	
						16.28	Cum

- 7 Providing and laying Cast in situ/Ready Mix cement concrete M-15 of trap/ granite/quartzite/gneiss metal for coping to plinth or parapet, moulded or chamfered as per drawing or as directed including steel centering, plywood/ steel formwork compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) With fine aggregate (Crushed sand VSI Grade)

SSR Item No.: 24.16

OTA	Coping	2	6.20	0.23	0.100	0.29	
		2	4.50	0.23	0.100	0.21	
						0.49	Cum

- 8 Providing and fixing in position TMT · FE · 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.

SSR Item No.: 26.33

	kg/cum		cum		kg	
FOOTING	60	x	0.97	=	58.32	
COLUMN	75	x	0.41	=	30.84	
BEAM & LINTEL	80	x	1.48	=	118.13	
COPING	30	x	0.49	=	14.77	
				kg	222.06	
					0.22	MT

- 9 Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days

SSR Item No.: 32.11

OTA	Plaster	1	6.66	0.90	5.99	
	Plaster	1	4.50	0.90	4.05	
					10.04	Sqm

- 10 Providing and laying vitrified mirror / glossy finish tiles decorative type having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006 (group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete.

Item No.	Item Of Work.	No	Length	Width	Depth	Quantity	Unit
1	2	3	4	5	6	7	8

SSR Item No. 33.40

OTA

1	6.66	4.50	29.97	
			29.97	Sqm

- 10 Providing and applying two coats of water proof cement paint of approved manufacture and of approved colour to old plastered surfaces including scaffolding if necessary, cleaning and preparing the surface, watering for two days etc complete.

SSR Item No. 35.14

OTA

Outer
Colour

2	6.66	0.90	11.99	
2	4.50	0.90	8.10	
			20.09	Sqm

Sectional Engineer

NAME OF WORK

**CONSTRUCTION OF OOTA INFRONT OF DR. BABASAHEB AMBEDKAR STATUE
PREMISES AT VILLAGE SAKHALI KHURD TQ.+DIST BULDANA**

RATE ANALYSIS

Item No.	Item of Work	Rate
----------	--------------	------

- 1 Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means

SSR Item No.- 21.02

Rs. 207.00
Total Rs. 207.00
Say Rs. 207.00

- 2 Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.

SSR Item No.- 21.38
Add for Lead

Rs. 1382.00

i) Rubble Stone 1.000 Cum @ 321.99

321.99
Total Rs. 1703.99
Say Rs. 1704.00

- 3 Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)

SSR Item No.- 24.01
Deduct For SCADA

Rs. 5830.00
126.00 = Rs. -126.00
5704.00

Add for Lead

i) Cement 4.400 Bag. @ 12.27
ii) Sand 0.470 Cum. @ 999.30
iii) Aggregate 0.90 Cum. @ 426.19

53.99
469.67
383.57
Total Rs. 6611.24
Say Rs. 6611.25

- 4 Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite/quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction and roughening the surface if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)

SSR Item No.- 25.50
Deduct For SCADA

Rs. 12269.00
126.00 = Rs. -126.00
12143.00

Add for Lead

i) Cement 7.000 Bag. @ 12.27
ii) Sand 0.425 Cum. @ 999.30
iii) Aggregate 0.90 Cum. @ 426.19

85.90
424.70
383.57
Total Rs. 13037.17
Say Rs. 13037.15

- 5 Providing fly ash brick masonry with conventional / I.S. type fly ash bricks in C.M. 1:6 in foundation and plinth including bailing out water manually striking joints, racking out joints watering and scaffolding etc. complete.

SSR Item No.- 27.12
Add for Lead

Rs. 6884.00

i) Cement 1.580 Bag. @ 12.27

19.39